




Public Meeting, July 28, 2021



Meeting Agenda

- Introductions
- Project Presentation
 - Overall Project Description
 - Project Goal
 - Project Area
 - Preliminary Schedule
 - Cost Approach
 - Design Elements
- Open Discussion/Questions
- Closing Remarks/Next Steps
- Crime Statistics





Overall Project Description

- Melrose Park Association is 2,000 home development with a population of just over 7,000 people. Melrose Park is one of the newer additions to the City of Fort Lauderdale; it was annexed in 2002. Currently there is no streetlighting in the development.
- The City is proposing to install 722 new FPL roadway LED streetlights.










Project Goal

This project will provide new streetlighting throughout the Melrose Park Neighborhood Association to enhance the pedestrian and roadway safety. The City is planning to use Florida Power & Light Company (FPL) street lighting program where the streetlighting cost is paid based on established monthly fees.



N.I.C.	E-02	E-03	E-04	E-05	E-06
E-07	E-08	E-09	E-10	E-11	E-12
E-13	E-14	E 15	© E	E-17	E-18
E-19	E-20	E-2	E 22	E-23	E-24
E-25	E-26	E-27	E-2 8	E-29	£-30
E-31	E-32	E-33	Ę-34	E-35	E-3 6
E-37	E-38	E-39	E-40	E-41	E-42



Project Area

 722 new streetlights are proposed to be installed throughout the entire Neighborhood Association limits and will be located within the City Right-Of-Way



Preliminary Schedule



Layout and photometric drawings are completed by the consultant

FPL is working on the engineering drawings and draft agreement to be completed in August 2021

Agreement approval and execution between City of Fort Lauderdale and FPL (February 2022)

FPL to start the lights installation in spring 2022 and to be completed in fall of 2023



Cost Approach

- The City is planning to use Florida Power & Light Company (FPL) street lighting program to implements the improvements where the streetlighting cost is paid based on established monthly fees.
- The monthly cost is currently estimated by FPL to be \$17,259 and is planned be paid by the City as part of the streetlight bill
- There is no proposed financial impact to the Melrose Park Neighborhood Association for this project, all costs are currently planned to be paid by the City. The agreement will require Commission approval.



LED Lighting Plan

City of Fort Lauderdale - Melrose Park


Going Green This plan reduces power consumption by: and that eliminates: or removing: cars from the road ²					
TOTAL			\$	- \$	17,258.9
otollotion Botollo			Evi-ti		Option 1
nstallation Details		select fixture:	Existing		Option 1
1		select fixture:		RSW	41 Watt 4000K
		fixture / pole:	1		1
		select pole:		Stan	dard Concrete
		Fixture*		\$	3,249.
Quantity:	723	Pole		\$	5,176.
FPL Conversion:	No	Maintenance		\$	932.0
Full/Hybrid:	Full	Energy**		\$	577.8
		Monthly Total		\$	9,936.
SUB TOTAL			\$	- \$	9,936.7
stallation Details			Existing		Proposed
		select wire:	SL-1 UCNP		SL-1 UCNP
Wire		Footage			
		select wire:	SL-1 UCUP	SL-1 UCUP	
		Footage			
		select wire:			LT-1 UC
		Footage			180750
		Total	\$	- \$	7,322.

AM 22-0223 Exhibit 3

Page 7 of 13







Design Elements

- Concrete Poles 22'-6" above ground (30' overall)
- 8' aluminum arm
- CREE RSW 41W LED light 5000 lumens, 4000K
- Concrete poles will provide attractive appearance and longevity, low maintenance versus wood poles



Design Elements


- CREE RSW 41W LED light 5000 lumens, 4000K
- ➤ LED lights are very energy efficient, reduce glare and provide optimized target illumination versus high pressure sodium lights

APPLICATIONS



Residential Street Lighting


As you leave or approach your driveway, the RSW Series, with WaveMax® Technology, reduces glare while delivering optimized target illumination. Residents no longer have to live with street lights shining into their living rooms and bedrooms at night.






Design Elements

- CREE RSW 41W LED light 5000 lumens, 4000K
- ➤ RSW light is best suited for residential streets, cost effective, has high color rendition 70 CRI
 - ➤ Higher CRI improves visibility , drivers can see nearby vehicles, surrounding areas and traffic signs better to avoid unsafe surroundings








Design Elements


- CREE RSW 41W LED light 5000 lumens, 4000K
 - > 5000 lumens lights will allow for more even light distribution and fewer poles

RSW SMALL

70-150W HPS REPLACEMENT




PERFORMANCE SUMMARY				
Initial Delivered Lumens: Up to 7,000 lumens				
Input Power: Up to 51 watts				
Color Rendering Index (CRI): 70 or 80 (3L/5L)				
CCT: 2700K (3L/5L), 3000K, 4000K, 5000K				
Dimensions: L: 20.7" (525mm) / W: 9.8" (249mm) / H: 5.0" (126mm)				
Weight: 9.4 lbs. [4.3kg]				





Open Discussion, Questions



Melrose Park Proposed Streetlighting Project

- Conceptual Project Costs Developed / Neighbor Support –
 October 2015
 - 97,100 linear feet of roadway / spacing of approximately 70 feet per light
 - * 1,387 streetlights required / approximately \$7,800 cost per light installed
 - Approximately \$11 million project using solar lighting
- Interest Survey Mailed to Community / Neighbor Support -September 15, 2016
 - * 1961 total mailings
 - * 454 responses received / 23% response rate
 - * 367 YES / 81% in favor of those that responded
 - * 83 NO / 18% not in favor of those that responded
 - * 4 Unmarked / No indication of preference
- Next Steps November 18, 2016
 - Transferred to Public Works Project Management Team
 - Public Works, along with Neighbor Support, working to solidify recommendations and refine costs
 - Lighting Consultant Required / Need to Identify Funding for Task Order