welcome to

Rehabilitation of North Airfield at Fort Lauderdale-Hollywood International Airport





CAM 19-0559 Exhibit 1 Page 1 of 13







Fort Lauderdale-Hollywood International Airport Today

35.9 million passengers in 2018

Total passenger traffic in 2018 increased 10.6% over 2017

FLL ranks 18th in total traffic and 10th in International traffic

New Service in 2018 to 21 new and existing markets

Three largest carriers at FLL are JetBlue, Southwest and Spirit with 65% of traffic







FLL Today




CAM 19-0559 Exhibit 1 Page 3 of 13





History

- Airport was originally established in 1929
- Airport became Naval Air Station Fort Lauderdale in 1942
- Portions of Runway 10L-28R date back to 1943
- Runway 10L-28R has been strengthened, lengthened and improved many times









Why?

- It has been 15 years since any major rehabilitation
- Runway 10L-28R was the only active runway for 18 months during South Runway (10R-28L) construction and experienced heavy usage
- The North Runway is in need of structural, drainage, safety, lighting and signage upgrades
- Improvements will increase rehabilitation cycle to 30 years













Project Benefits

Reduces Rehabilitation Cycles

Improves and Enhances Runway Safety Areas

Reduces Probability of Runway Incursions


Improves Lighting, Signage, and Navigational Aids

Improves Drainage, including raising Runway Centerline





General Overview of Project



LEGEND



PAVEMENT DEMOLITION



SHOULDER NEW PAVEMENT



TAXIWAY NEW PCC



RUNWAY NEW PCC



NO TAXI ISLANDS



TAXIWAY MILL AND OVERLAY



RUNWAY NEW ASPHALT PAVEMENT



TAXIWAY NEW ASPHALT PAVEMENT



NEW EMAS BEDS


CAM 19-0559 Page 7 of 13





welcome to


Runway Keel Replacement Typical Section







Overall Phasing Plan









Project Schedule

Project Award

February 26, 2019

Begin
Phase 2 Taxiway A
Work

March 25, 2019

Begin
Phase 3 Runway
Closure

June 3, 2019

Phase 4 - Taxiway B & C Work

October 2019 March 2020 Overall
Project
Substantial
Completion

March 2020









CAM 19-0559 Exhibit 1 Page 11 of 13







Summary



Construction Budget: \$64.4 million

Up to four months of Runway closure

Locally planned, designed and constructed

15 subcontractors/150-200 workers during Runway closure

> CAM 19-0559 Page 12 of 13







Questions

Technical questions – BCAD Project Manager: 954-359-6973

Aircraft noise comments – Noise Hotline: 866-822-7910

Public Information Officer: 954-359-6116