

Revised Quote Station 1 FLAP GATES

MWI Pumps 7775 SW 9th. Street (Oslo Road) Vero Beach, FL 32968 Phone: (772) 770-0004 Fax: (772) 770-1096	Date: 5-19-20 Quote Number: 20-0014 Quotation validity unless otherwise noted expires 30 days from date shown
--	--

Project:	Station 1 Three New Flap gates	Terms: Net 30 each Invoice
Quote To:	Kevin Scott 954-828-7868 City of Fort Lauderdale 949 N.W. 38th Street, Fort Lauderdale, FL 33309	FOB: "Station 1" Jobsite
Delivery:	Approximately 6 weeks after first gate removal	Customer PO:
		Quoted By: Bill Miller 954-682-2062

Item	Qty.	Description	Unit Price	Total Price
A	1	Remove one 30" flap-gate and install customer supplied pig in discharge. This includes the launch to access the gate from the water side.	\$20,739.00	\$20,739.00
B	1	Build (three) new 30" flap-gates using 316SS channel and two layers of UHMW material per customer request.		
C	1	Remove pig and install new replacement gate Remove the two remaining gates and replace with new. This includes the launch to perform work from the water side.		
D	1	A Watercraft Insurance Policy meeting the City's conditions is include. Note: This quote only includes work with the flap gates, any additional items such as the wall thimbles/seats would be addressed during inspection and removal of the old flap-gates. Work to be done during Low Tide.		

WE LOOK FORWARD TO YOUR FAVORABLE CONSIDERATION

Please note that prices do not include applicable Sales Tax, Fees, Installation or Freight unless otherwise noted

Quote Station 1

MWI Pumps 7775 SW 9th. Street (Oslo Road) Vero Beach, FL 32968 Phone: (772) 770-0004 Fax: (772) 770-1096	Date: 5-6-20 Quote Number: 20-0012 Quotation validity unless otherwise noted expires 30 days from date shown
--	---

Project:	Station 1 (2) 30" Vertical Service and Repair	Terms: Net 30 each Invoice
Quote To:	Kevin Scott 954-828-7868 City of Fort Lauderdale 949 N.W. 38th Street, Fort Lauderdale, FL 33309	FOB: "Station 1" Jobsite
Delivery:	Turnaround time each pump approximately 48 days and New motors approximately 11-13 weeks after receipt of order.	Customer PO: Quoted By: Bill Miller 954-682-2062

Item	Qty.	Description	Unit Price	Total Price
A	2	Furnish transport, field & shop labor and materials to perform the following services to 30" vertical pump. <ul style="list-style-type: none"> • Pick-up and return pump from customer site • Disassemble and inspect pump • Replace main shaft, head shaft & coupling with 316 SS new material and machining • Replace shaft bearings with Thordons • Replace steady bearing • Replace motor hood plate to accept new motor • Check impeller and balance • Weld on 316SS bars on intake • Supply all new 316 SS hardware 	\$26,524.00	\$53,048.00
B	2	Provide new 150HP, VHS, 5008PA, 720rpm, WP1 enclosure, 460v, 3 phase, NRR, premium efficiency electric motor (4,100LBS) Note: Any additional items found after disassembly will be quoted and pre-approved before completed Pricing is based on a single unit completed at a time. Customer supplied crane	\$44,291.00	\$88,582.00

WE LOOK FORWARD TO YOUR FAVORABLE CONSIDERATION
Please note that prices do not include applicable Sales Tax, Fees, Installation or Freight unless otherwise noted

Quote Station 2

MWI Pumps 7775 SW 9th. Street (Oslo Road) Vero Beach, FL 32968 Phone: (772) 770-0004 Fax: (772) 770-1096	Date: 5-6-20 Quote Number: 20-0013 Quotation validity unless otherwise noted expires 30 days from date shown
--	---

Project:	Station 2 (1) 30" and (1) 24" Jockey Remove & Inspect	Terms: Net 30 each Invoice
Quote To:	Kevin Scott 954-828-7868 City of Fort Lauderdale 949 N.W. 38th Street, Fort Lauderdale, FL 33309	FOB: "Station 2" Jobsite
Delivery:	Turnaround time each pump approximately 48 days	Customer PO: Quoted By: Bill Miller 954-682-2062

Item	Qty.	Description	Unit Price	Total Price
A	1	Furnish transport, field & shop labor to perform the following services to 30" vertical pump. <ul style="list-style-type: none"> • Unbolt and remove pump and re-install • Disassemble and inspect pump parts • Assess all parts and quote recommended action required. • Check impeller and balance and reassemble • On re-installation install motor and adjust shaft 	\$8,600.00	\$8,600.00
B	1	Furnish transport, field & shop labor to perform the following services to 24" vertical Jockey pump. <ul style="list-style-type: none"> • Unbolt and remove pump and re-install • Disassemble and inspect pump parts • Assess all parts and quote recommended action required • Check impeller and balance and reassemble • On re-installation install motor and adjust shaft <p>Price is for both pumps being pulled same day and reinstalled same day. Customer supplied crane</p>	\$8,600.00	\$8,600.00

WE LOOK FORWARD TO YOUR FAVORABLE CONSIDERATION
Please note that prices do not include applicable Sales Tax, Fees, Installation or Freight unless otherwise noted

Sub-Contractor List

R & S METALWORKS & CO. LLC

5690 Carlton Road.

Port Saint Lucie, FL 34987

Scott Snowden

P: 772-466-3303